

PRINCESS DRIVE, LIVERPOOL

Details: 14,200m² of Milepave™

Contract Date and Duration: Sep 2025,
three weeks under partial road closure



EXISTING ISSUES WITH SITE

Both sides of the dual carriageway were in a heavily deteriorated condition, with widespread potholes and delamination present across all lanes. There was also frequent reflective cracking in the existing overlay from the concrete construction below.

SITE DETAILS AND USAGE

It is a busy dual carriageway that serves as a key route linking the residential areas with the wider city, including access towards the city centre and major surrounding roads. Situated near a large supermarket, it experiences consistently high traffic volumes.



BENEFITS OF UTILISING MILEPAVE™

The material is ideal for the resurfacing of this dual carriageway, offering an effective solution for overlaying existing concrete carriageways. Its pre- and post-jointing system introduces flexibility over the underlying concrete joints, helping to accommodate movement and reduce reflective cracking. Milepave™ boasts all three performance elements needed for a successful concrete overlay by being strong, flexible and sealed.



BEFORE



AFTER



BEFORE



AFTER



